

WIDTH VARIES  
RAMP "H"

EDGE PAVEMENT EXIT RAMP I-90-94  
 $R=377.30'$   
 $N 16^{\circ}45'53'' W$   
 $205.86'$

$R=378.02'$   
 $(N 16^{\circ}38'35'' W, 205.86')$

PARCEL AREA = 107,050 SQ. FT.  
(2.4567 ACRES)


DAENTL ROAD  
R/W WIDTH VARIES

**LEGEND**

- SOLID IRON ROD FOUND (0.75" Dia. unless noted)
- 3/4"x18" SOLID IRON ROD SET  
1.5 Lbs./LINEAL FOOT.
- ( ) INDICATES RECORDED AS DISTANCES ARE  
MEASURED TO THE NEAREST HUNDREDTH OF A FOOT.
- ⊕ HYDRANT
- ⊙ POWER POLE
- ⊛ LIGHT POLE
- ⊙ MANHOLE
- OH — OH — OVERHEAD ELECTRIC

**KEY**

- EXISTING ASPHALT PAVEMENT
- EXISTING CONCRETE
- EXISTING CONCRETE



ISSUANCE/REVISION	DATE
SITE PLAN APPROVAL	06-04-2022

818 N Meadowbrook Ln  
Waukegan, WI 53597  
phone (608) 849-9378  
www.pe-wi.com

**PROFESSIONAL ENGINEERING** LLC

TOWN OF BURKE, WISCONSIN

**TRUCK WASH  
EXISTING CONDITIONS**

6011 US HWY 51 (DAENTL RD)

**C100**