

June 28, 2018

Rich McVicar, ENP Technical Services Manager Dane County Public Safety Communications 210 Martin Luther King Jr Blvd Rm 109 Madison, WI 53703-3342

## RE: Alliant Energy Center and Exhibition Hall Budgetary Quote - BAFO

The following is our budgetary quote to install a VHF bi-directional amplifier and distributed antenna system for each building to improve communications on the Danecom radio system.

This quote includes all labor, travel, parts, testing and verification.

## **Summary:**

<u>Facility</u>			<b>Price</b>
Alliant Energy Center		\$	51,671.30
Exhibition Hall		\$	48,207.10
	Total.	Φ	00 070 40

Total: \$ 99,878.40

## **Alliant Energy Center:**

<b>Qty</b>	<u>Description</u>	<u>Price</u>	<b>Extended</b>
2	VHF BDA, 80dB	\$10,826.11	\$21,652.23
2	Isolator, WB VHF DL 50 Watt	\$803.59	\$1,607.18
4	Cable RG-142 Critical Length Cable	\$111.61	\$446.45
4	EMR System Integration	\$171.14	\$684.55
2	Splitter 2-Way, 150-175MHz	\$258.94	\$517.88
1	Donor Antenna, VHF Wide Band	\$339.53	\$339.53
1	Non-Penetrating Roof Mount	\$175.00	\$175.00
1	Roof Mount Mat	\$25.00	\$25.00
8	Bricks	\$5.00	\$40.00
1	Mounting Clamp Kit	\$61.07	\$61.07
1	Polyphaser Lightning Protection	\$66.73	\$66.73
3050'	1/2" Non-Plenum Cable	\$1.33	\$4,052.14
44	1/2" N-Male Connectors	\$13.84	\$609.09
100'	Low Loss Coax Cable	\$0.96	\$95.71
2	Coax Connectors, N-Male	\$4.09	\$8.17
16	132-174, 380-570, 700-960 Flat Ant	\$141.43	\$2,262.86
5	Directional Coupler, 3dB, 147-960MHz	\$157.67	\$788.36
6	Directional Coupler, 6dB, 147-960MHz	\$157.67	\$946.03
4	Directional Coupler, 10B, 147-960MHz	\$157.67	\$630.69
10	RG142 Jumper, 3'	\$36.43	\$364.29
6	Self-Locking Hangers, 100 Pack	\$99.73	\$598.37

Madison, WI 53719 (608) 271-4848 / (800) 356-3200



1	FCC Class B Amplifier Registration	\$200.00	\$200.00
1	Installation	\$11,000.00	\$11,000.00
1	Commissioning and Testing	\$1,500.00	\$1,500.00
1	Project Management	\$3,000.00	\$3,000.00
		Sub Total	\$51,671.30

## **Exhibition Hall:**

Qty	<u>Description</u>	<b>Price</b>	<b>Extended</b>
2	VHF BDA, 80dB	\$10,826.11	\$21,652.23
2	Isolator, WB VHF DL 50 Watt	\$803.59	\$1,607.18
4	Cable RG-142 Critical Length Cable	\$111.61	\$446.45
4	EMR System Integration	\$171.14	\$684.55
2	Splitter 2-Way, 150-175MHz	\$258.94	<i>\$517.88</i>
1	Donor Antenna, VHF Wide Band	\$339.46	\$339.46
1	Mounting Clamp Kit	\$61.07	\$61.07
1	Wall Mount Bracket, 6" Heavy Duty	\$230.10	\$230.10
1	Polyphaser Lightning Protection	\$66.73	\$66.73
2200'	1/2" Non-Plenum Cable	\$1.33	\$2,922.86
16	1/2" N-Male Connectors	\$13.84	\$221.49
100'	Low Loss Coax Cable	\$0.96	\$95.71
2	Coax Connectors, N-Male	\$4.09	\$8.17
7	132-174, 380-570, 700-960 Flat Ant	\$141.43	\$990.00
3	Directional Coupler, 3dB, 147-960MHz	\$157.67	\$473.01
1	Directional Coupler, 6dB, 147-960MHz	\$157.67	\$157.67
1	Directional Coupler, 10B, 147-960MHz	\$157.67	\$157.67
1	Directional Coupler, 15dB, 147-960MHz	\$157.67	\$157.67
6	RG142 Jumper, 3'	\$36.43	\$218.57
5	Self-Locking Hangers, 100 Pack	\$99.73	\$498.64
1	FCC Class B Amplifier Registration	\$200.00	\$200.00
1	Lift Rental	\$1,000.00	\$1,000.00
1	Installation	\$11,000.00	\$11,000.00
1	Commissioning and Testing	\$1,500.00	\$1,500.00
1	Project Management	\$3,000.00	\$3,000.00
	-	Sub Total	\$48,207.10

Note: The items in italics have a lead time of about 8 weeks.

If you have any questions, please email gary.pelletier@gencomm.com or call 608-310-7122.

Sincerely,

Gary E. Pelletier Gary E. Pelletier

General Manager / Systems Engineer