





## **Specifications**

- $^{\bullet}$  60' x 80' (4,800 S.F. building with 14' x 80' 1,120 S.F. open-side lean) 5,920 S.F. total area.
- Building inside clearance (floor to rafters): 16'
- Wood frame construction
- Steel roof over ½" O.S.B and felt
- LP Brand Diamond Kote vertical board & batten siding
- ${}^{\bullet}\,\mathcal{V}_{\!2}{}''$  O.S.B. exterior wall sheeting with Tyvek vapor barrier
- •8" concrete frost wall
- 6" compacted gravel floor









## Cost, Funding & Project Approval **Status**

- Total project cost: \$331,000
  Cash on-hand plus pledges as of April 25, 2023: \$236,000
  Balance needed to fully-fund the project: \$95,000
- The Friends are working closely with the Dane County Land and Water Resources Department on final approval and permitting

  • We hope to begin construction in July of 2023